BANK OF BARODA-NewTown,
Kolkata

BOQ OF CIVIL, FURNISHING, SANITARY PLUMBING, ELECTRICAL, LAN WORK FOR BANK OF BARODA - NEWTOWN,KOL

Section E : LAN cabling Work

Sl. No.	Description of Item	Qty.	Unit	Rate (Rs.)	Amount (Rs.)
1	Supply & laying OF 4PAIR UTP CAT6 CABLE PVC	600	Mtrs		
2	Supply & laying of 2 pair **telephone cable** througrout / 19mm conduct pipe	300	RM		
3	Supply & fixing **telephone socket outlet RJ 11** type make MK	10	Nos		
4	LAN CONDUIT : Providing & Fixing 25mm bore rigid PVC conduit to accommodate 4nos 4 Pair LAN UTP CATV cable partly laid during and partly concealed over false ceiling/in furniture/ in brick wall/ in floor including making good damages . The rate should include supply and laying of all materials like conduit Pipe, saddles, hooks inspection boxes etc. and any other materials to complete the wiring, & making connection.	300	RM		
5	Supply & Laying Termination of Cat6 RJ45 Module - Data	16	No		
6	Supply & Laying Scanning of Data Nodes	16	No		
7	SUPPLY & LAYING CAT6 RJ45 TOOLESS SKT 1 MOD	16	No		
8	SUPPLY & LAYING PATCH PANEL UTP CAT6 TOOLESS 24RJ	2	No		
9	SUPPLY & LAYING CAT6 UTP PATCH CORD 1M	16	No		
10	SUPPLY & LAYING CAT6 UTP PATCH CORD 2M	16	No		
11	Supply & Laying Dual Port Face Plate	16	No		
12	Supply & Laying Flush Box	16	No		
13	Supply & Laying OF CRONE BOX	4	NO		
		TOTAL		**Rs.**	