

Sr No	Item Description	QTY	Unit	Rate	Total
1	Supply and Installation, testing and Commissioning of of <b>60kVA/54kW</b> Modular Hot swappable UPS expandable minimum up to 100KVA UPS system in N+1 , each module of Minimum 20kVA , UPS with 3PH input and 3PH output along with Modbus card as per technical specification. Bidder to provide UPS frame for of minimum 100KVA considering future expansion all complete as required and as per the final direction and the approval of the Consultants/Bank . Approved Make are Schneider/Vertiv/ABB/Delta/Eaton	No	2		
2	12V/2V SMF Hybrid Gel VRLA Battery Set for 60 minutes back up with min 110400 VAH, C-10 rated , UL Certified inclusive of battery rack, interconnecting cables , battery MCCB in Enclosure for each string with Three Years Warrantee on battries all complete as required and as per the final direction and the approval of the consultants/Bank. The approved make of the battries are RAYS/HOPPECKE/C&D/QUANTA make	Set	2		
3	60Kva Isolation Transformer of Datson or as per UPS OEM Approved make to be connected at output side of UPS with Input MCCB & Digital VAF meter (K-13 rating, Copper winding all complte as required and as per the fianl direction and the approval of the Consultants/Bank.	No	2		
4	Rates for CAMC of both UPS along with batteries and Isolation Transformer system for 1st year after expiry of Defects Liability Period of 1 year post installation	LS	1		
5	Rates for CAMC of both UPS along with batteries and Isolation Transformer system for 2nd year after expiry of Defects Liability Period of 2nd year post installation	LS	1		
6	Rates for CAMC of both UPS along with batteries and Isolation Transformer system for 3rd year after expiry of Defects Liability Period of 3rd year post installation	LS	1		
	<b>TOTAL</b>				
	<b>DISCOUNT IF ANY</b>				
	<b>GRAND TOTAL AFTER DISCOUNT</b>				

**Please note: Rates quoted are to be excluding GST  
GST will be paid extra as per Govt's extant guidelines**