BANK OF BARODA

Baroda Apex Academy

Design, supply, installation, testing and commissioning of Kitchen Equipment at Baroda Apex Academy Building at Ahmedabad

Technical Specifications

Section- 2

Revised Technical Specification of Kitchen Equipment

Item No.01

Platform Weighing scale (MLP 1) : Supply, Installation and Commissioning of weighing scale 200 kg capacity which includes preparation of shop drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling and storage at site, final assembly at designated rooms at any floor level as per the Technical Specification. The top shall be made of SS. Heavy duty make. ISI Approved. Make: MARUTI / PUNIT / ESSEE.

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:

The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No.02

SS sink With Table with Faucet (MLP 2) : Supply, Installation and Commissioning of SS sink with table equipment which includes preparation of shop drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling and storage at site, final assembly at designated rooms at any floor level as per the Technical Specification. The top shall be made of 16 SWG SS 304 with 150mm high back splash. The Sink shall be of size 450mm x 450mm x450mmdeep made of 16 SWG SS 304. Interior frame structure to be made of SS 16 swg . 25mm or 30mm Square Pipe and additional frame support of SS 16 SWG. Uprights & Cross Bracing to be made of SS 16 SWG .25mm Or 30MM Square Pipe 304 Quality . All Legs to be made of SS 16 SWG . 40mm 304 quality Square Pipe with adjustable nylon bolts.All equipment top to be made from 16 swg with all sides down bedded twice within ss angle/SS pipe support..All bottom and upper shelves to be made from 18swg with all sides down bedded twice within ss angle/ss pipe support.Side covers to be made from 18 swg.NO MILD STEEL TO BE USED ANY WHERE IN THE CONSTRUCTION.

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:

The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No.03

SS Storage Rack with Four Shelf (SR-01): Supply, Installation and Commissioning of SS Storage Rack with Four Shelf equipment which includes preparation of shop drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling and storage at site, final assembly at designated rooms at any floor level as per the Technical Specification. : The top shall be made of 16 SWG SS 304 . Interior frame structure to be made of SS 16 swg . 25mm or 30mm Square Pipe and additional frame support of SS 16 SWG. . All Legs to be made of SS 16 SWG . 40mm 304 quality Square Pipe with adjustable nylon bolts.All equipment top to be made from 16 swg with all sides down bedded twice within ss angle/SS pipe support..All bottom and upper shelves to be made from 18swg with all sides down bedded twice within ss angle/ss pipe support.Side covers to be made from 18 swg.NO MILD STEEL TO BE USED ANY WHERE IN THE CONSTRUCTION. All shelves to have stiffner support.All equipment to be made on 1.5" dia. s.s. pipe with adjustable nylon bolt. 900x500x1800

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:

The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No.04-

SS storage atta bin with Wheels (SR-02): Supply, Installation and Commissioning of SS storage Atta Bin with wheels & Lid equipment which includes preparation of shop drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling and storage at site, final assembly at designated rooms at any floor level as per the Technical Specification. The top shall be made of 16 SWG SS 304 , Interior frame structure to be made of SS 16 swg . 25mm or 30mm Square Pipe and additional frame support of SS 16 SWG. .All equipment top to be made from 16 swg with all sides down bedded twice within ss angle/SS pipe support..Lid to be made from 18 swg with bottom wheels for easy movement.All bottom and upper shelves to be made from 18swg with all sides down bedded twice within ss angle/ss pipe support.Side covers to be made from 18 swg.NO MILD STEEL TO BE USED ANY WHERE IN THE CONSTRUCTION. 500x500x600

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:

The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No.5

SS onion Potato Bin with wheel (SR-03): Supply, Installation and Commissioning of SS Onion Potato Bin with wheels equipment which includes preparation of shop drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling and storage at site, final assembly at designated rooms at any floor level as per the Technical Specification. The top shall be made of 16 SWG SS 304 , Interior frame structure to be made of SS 16 swg . 25mm or 30mm Square Pipe and additional frame support of SS 16 SWG. .All equipment top to be made from 16 swg with all sides down bedded twice within ss angle/SS pipe support..Lid to be made from 18 swg with bottom wheels for easy movement.All bottom and upper shelves to be made from 18swg with all sides down bedded twice within ss angle/ss pipe support.Side covers to be made from 18 swg.NO MILD STEEL TO BE USED ANY WHERE IN THE CONSTRUCTION. 1100x600x850

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:

The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No.06

Weighing Scale 100 Kg 500x500 mm size (SR-04): Supply, Installation and Commissioning of weighing scale 300 kg capacity which includes preparation of shop drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling and storage at site, final assembly at designated rooms at any floor level as per the Technical Specification. The top shall be made of SS .Heavy duty make . ISI Approved. Make: Maruti /PUNIT/ESSEE.

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:

The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No. 07

SS Dunnage Rack (SR-05): Supply, Installation and Commissioning of SS Dunnage Rack equipment which includes preparation of shop drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling and storage at site, final assembly at designated rooms at any floor level as per the Technical Specification. The top shall be made of 16 SWG SS 304. .All equipment top to be made from 16 swg .All bottom and upper shelves to be made from 18swg with all sides down bedded twice within ss angle/ss pipe support.Side covers to be made from 18 swg.NO MILD STEEL TO BE USED ANY WHERE IN THE CONSTRUCTION. 700x700x300.

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:

The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No.8

Sprial Type Dough Kneder 10Kg (Imported) (PA-01) : Supply, Installation and Commissioning of Spiral Type Dough Kneder 10KG equipment which includes preparation of shop drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling and storage at site, final assembly at designated rooms at any floor level as per the Technical Specification. 1.1 KW Power , Total weight 88 kg of Machine , spiral speed 325/270/190RPM , outside Dimensions : 366x690x810 mm, Digital Control Panel , The material of mixing area meets the request of Food hygiene. Bowl is made of SS 304 with Polishing. Make: FALCON / SPAR / EZYCOOK.

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:

The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No. 9

Tilting type wet grinder 10Kg (Custom) (PA-02) : Supply, Installation and Commissioning of Tilting type wet grinder 10 kg equipment which includes preparation of shop

drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling and storage at site, final assembly at designated rooms at any floor level as per the Technical Specification. : SS Drum with Commercial Coconut Scraper Attached , with commercial Gear Boxes Drives with 1 year machine warranty , with Natural Black stones , 1.0 Hp motor. Make: Santosh / Laxmi / Leenovo.

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:

The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No.10

Potato peeler (10 kg) (PA-03): Supply, Installation and Commissioning of Potato Peeler 10 Kg equipment which includes preparation of shop drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling and storage at site, final assembly at designated rooms at any floor level as per the Technical Specification.: 10 kg capacity at a time , 1 hp motor , Duration time 3-5 Min . SS 304 full body structure. Standard Company Motor. Make: Leenovo / Pragati / Nirali.

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:

The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No. 11

Pulveriser (3 HP) (PA-04): Supply, Installation and Commissioning of Pulverizer SS equipment which includes preparation of shop drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling and storage at site, final assembly at designated rooms at any floor level as per the Technical Specification.: 3 Hp Pulverizer machine , 9" x4" Chamber Size , SS body , Beater : SS make , Jali 5 SS make , Motor : 2800 RPM , Capacity : 50-90 Kg . Make: Leenovo / Pragati / Nirali.

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:

The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No.12

SS work table with sink (1000x600x850+150)mm (PA-05): Supply, Installation and Commissioning of SS sink with table equipment which includes preparation of shop drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling and storage at site, final assembly at designated rooms at any floor level as per the Technical Specification. The top shall be made of 16 SWG SS 304 with 150mm high back splash. The Sink shall be of size 450mm x 450mm x450mmdeep made of 16 SWG SS 304. Interior frame structure to be made of SS 16 swg . 25mm or 30mm Square Pipe and additional frame support of SS 16 SWG. Uprights & Cross Bracing to be made of SS 16 SWG .25mm Or 30MM Square Pipe 304 Quality . All Legs to be made of SS 16 SWG . 40mm 304 quality Square Pipe with adjustable nylon bolts. All equipment top to be made from 16 swg with all sides down bedded twice within ss angle/SS pipe support..All bottom and upper shelves to be made from 18swg with all sides down bedded twice within ss angle/ss pipe support. Side covers to be made from 18 swg. NO MILD STEEL TO BE USED ANY WHERE IN THE CONSTRUCTION.

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:

The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No.13

SS Under counter Refrigerator (PA-07) : Supply, Installation and Commissioning of SS sink with table equipment which includes preparation of shop drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling and storage at site, final assembly at designated rooms at any floor level as per the Technical Specification. The top shall be made of 16 SWG SS 304 with 150mm high back splash. Interior frame structure to be made of SS 16 swg . 25mm or 30mm Square Pipe and additional frame support of SS 16 SWG. . All Legs to be made of SS

16 SWG . 40mm 304 quality Square Pipe with adjustable nylon bolts. All equipment top to be made from 16 swg with all sides down bedded twice within ss angle/SS pipe support. All bottom and upper shelves to be made from 18swg with all sides down bedded twice within ss angle/ss pipe support. Side covers to be made from 18 swg. NO MILD STEEL TO BE USED ANY WHERE IN THE CONSTRUCTION. Compressor : Emerson make. (1200x600x850+150) mm.

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:

The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No.14

Two Door Vertical Refrigerator (500 ltr) (SRC-02) : Supply, Installation and Commissioning of Two Door Vertical Refrigerator which includes preparation of shop drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling and storage at site, final assembly at designated rooms at any floor level as per the Technical Specification. Temp: +2 to +8. Compressor : Emerson make.

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect. The finished surface including the cover surface if any will be measured for payment.
- The measurement shall be taken in **each set** as per size correct to two places of decimal for the length and breadth in centimeters.

Rates:

The rates for the item shall include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No.15

SS Tilting type Bratt pan (100 ltr) (MK-01) : Supply, Installation and Commissioning of SS Tilting type Bratt pan which includes SS 304 2.5mm for Pan body / SS 304 12mm bottom plate / SS 304 1.2mm for both side control box and 1 mm for removable panel, RV burner / pilot burner , needle control valve , copper pigtail etc. M.S tata 'c' class 22 mm pipe for mani fold, water faucet will be mounted on the R.H.S control box with 1/2"bsp 1 mtr water inlet flexible pipe. preparation of shop drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling

and storage at site, final assembly at designated rooms at any floor level as per the Technical Specification.

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:

The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No.16

Sujata juicer machine (900 watt) (MK-10) : Supply, Installation and Commissioning of sujata juicer machine which includes preparation of shop drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling and storage at site, final assembly at designated rooms at any floor level as per the Technical Specification.

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:

The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No.17

SS table with 1 Undershelf (700x700x850+150) mm (MK-02): Supply, Installation and Commissioning of SS Service table with 1 U/s with Four Shelf equipment which includes preparation of shop drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling and storage at site, final assembly at designated rooms at any floor level as per the Technical Specification. : The top shall be made of 16 SWG SS 304. Interior frame structure to be made of SS 16 swg. 25mm or 30mm Square Pipe and additional frame support of SS 16 SWG. All Legs to be made of SS 16 SWG. 40mm 304 quality Square Pipe with adjustable nylon bolts. All equipment top to be made from 16 swg with all sides down bedded twice within SS angle/SS pipe support. All bottom and upper shelves to be made from 18swg with all sides down bedded twice within SS angle/SS pipe support. Side covers to be made from 18 swg. NO MILD STEEL TO BE USED ANY WHERE IN THE CONSTRUCTION. All shelves to have stiffner support. All equipment to be made on 1.5" dia. s.s. pipe with adjustable nylon bolt.

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:

The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No.18

SS Gas range for Chinese food with 1 Under Shelf (1200x700x850+150) mm (MK-03) : Supply, Installation and Commissioning of SS Chinese Burner Gas Range with 1 U/s equipment which includes preparation of shop drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling and storage at site, final assembly at designated rooms at any floor level as per the Technical Specification. : The top shall be made of 16 SWG SS 304 . Interior frame structure to be made of SS 16 swg. 25mm or 30mm Square Pipe and additional frame support of SS 16 SWG. All Legs to be made of SS 16 SWG . 40mm 304 quality Square Pipe with adjustable nylon bolts. All equipment top to be made from 16 swg with all sides down bedded twice within ss angle/SS pipe support. All bottom and upper shelves to be made from 18swg with all sides down bedded twice within ss angle/ss pipe support. Side covers to be made from 18 swg. NO MILD STEEL TO BE USED ANY WHERE IN THE CONSTRUCTION. All shelves to have stiffner support. All equipment to be made on 1.5" dia. s.s. pipe with adjustable nylon bolt. All burners to be provided with ss spillage trays with s.s. handles. All burners and regulators to be sourced from ISI mark suppliers. All pan support grills to be made from heavy duty C.I.

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:

The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No. 19

SS table with Sink (600x1000x850+150) mm (MK-04): Supply, Installation and Commissioning of SS sink with table equipment which includes preparation of shop drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling and storage at site, final assembly at designated rooms at any floor level as per the Technical Specification. The top shall be made of 16 SWG SS 304 with 150mm high back splash. The Sink shall be of size 450mm x

450mm x450mmdeep made of 16 SWG SS 304. Interior frame structure to be made of SS 16 swg . 25mm or 30mm Square Pipe and additional frame support of SS 16 SWG. Uprights & Cross Bracing to be made of SS 16 SWG .25mm Or 30MM Square Pipe 304 Quality . All Legs to be made of SS 16 SWG . 40mm 304 quality Square Pipe with adjustable nylon bolts.All equipment top to be made from 16 swg with all sides down bedded twice within ss angle/SS pipe support..All bottom and upper shelves to be made from 18swg with all sides down bedded twice within ss angle/ss pipe support.Side covers to be made from 18 swg.NO MILD STEEL TO BE USED ANY WHERE IN THE CONSTRUCTION.

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:

The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No.20

SS Two Burner Gas range with 1 Under shelf (1200x700x850+150) mm (MK-05) : Supply, Installation and Commissioning of SS Two Burner Gas Range with 1 U/s equipment which includes preparation of shop drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling and storage at site, final assembly at designated rooms at any floor level as per the Technical Specification. : The top shall be made of 16 SWG SS 304 . Interior frame structure to be made of SS 16 swg . 25mm or 30mm Square Pipe and additional frame support of SS 16 SWG. . All Legs to be made of SS 16 SWG . 40mm 304 quality Square Pipe with adjustable nylon bolts. All equipment top to be made from 16 swg with all sides down bedded twice within ss angle/SS pipe support..All bottom and upper shelves to be made from 18swg with all sides down bedded twice within ss angle/ss pipe support. Side covers to be made from 18 swg.NO MILD STEEL TO BE USED ANY WHERE IN THE CONSTRUCTION.All shelves to have stiffner support.All equipment to be made on 1.5" dia. s.s. pipe with adjustable nylon bolt.All burners to be provided with ss spillage trays with s.s. handles.All burners and regulators to be sourced from ISI mark suppliers. All pan support grills to be made from heavy duty C.I.

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:

The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No.21

SS table with 1 Undershelf (600x700x850+150) mm (MK-06): Supply, Installation and Commissioning of SS Service table with 1 U/s equipment which includes preparation of shop drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling and storage at site, final assembly at designated rooms at any floor level as per the Technical Specification. : The top shall be made of 16 SWG SS 304 . Interior frame structure to be made of SS 16 swg . 25mm or 30mm Square Pipe and additional frame support of SS 16 SWG. All Legs to be made of SS 16 SWG . 40mm 304 quality Square Pipe with adjustable nylon bolts. All equipment top to be made from 16 swg with all sides down bedded twice within ss angle/SS pipe support..All bottom and upper shelves to be made from 18swg with all sides down bedded twice within ss angle/ss pipe support.Side covers to be made from 18 swg.NO MILD STEEL TO BE USED ANY WHERE IN THE CONSTRUCTION. All shelves to have stiffner support. All equipment to be made on 1.5" dia. s.s. pipe with adjustable nylon bolt.

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:

The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No. 22

SS table with 1 Undershelf (600x700x850+150) mm (MK-07): Supply, Installation and Commissioning of SS Service table with 1 U/s with Four Shelf equipment which includes preparation of shop drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling and storage at site, final assembly at designated rooms at any floor level as per the Technical Specification. : The top shall be made of 16 SWG SS 304 . Interior frame structure to be made of SS 16 swg. 25mm or 30mm Square Pipe and additional frame support of SS 16 SWG. All Legs to be made of SS 16 SWG . 40mm 304 quality Square Pipe with adjustable nylon bolts.All equipment top to be made from 16 swg with all sides down bedded twice within ss angle/SS pipe support..All bottom and upper shelves to be made from 18swg with all sides down bedded twice within ss angle/ss pipe support.Side covers to be made from 18 swg. NO MILD STEEL TO BE USED ANY WHERE IN THE CONSTRUCTION. All shelves to have stiffner support. All equipment to be made on 1.5" dia. s.s. pipe with adjustable nylon bolt.

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:

The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No.23

SS Storage Rack with Four Shelf (1500x650x1800) mm (MK-08) : Supply, Installation and Commissioning of SS Storage Rack with Four Shelf equipment which includes preparation of shop drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling and storage at site, final assembly at designated rooms at any floor level as per the Technical Specification. : The top shall be made of 16 SWG SS 304 . Interior frame structure to be made of SS 16 swg. 25mm or 30mm Square Pipe and additional frame support of SS 16 SWG. All Legs to be made of SS 16 SWG . 40mm 304 quality Square Pipe with adjustable nylon bolts. All equipment top to be made from 16 swg with all sides down bedded twice within ss angle/SS pipe support..All bottom and upper shelves to be made from 18swg with all sides down bedded twice within ss angle/ss pipe support. Side covers to be made from 18 swg. NO MILD STEEL TO BE USED ANY WHERE IN THE CONSTRUCTION. All shelves to have stiffner support. All equipment to be made on 1.5" dia. s.s. pipe with adjustable nylon bolt.

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:

The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No.24

SS table with 2 Undershelf (1200x650x850+150) mm (MK-09): Supply, Installation and Commissioning of SS table with 2 U/s lockable Door equipment which includes preparation of shop drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling and storage at site, final assembly at designated rooms at any floor level as per the Technical Specification. : The top shall be made of 16 SWG SS 304 . Interior frame structure to be made of SS 16 swg . 25mm or 30mm Square Pipe and additional frame support of SS 16 SWG.. All Legs to be made of SS 16 SWG . 40mm 304 quality Square Pipe with adjustable nylon

bolts. All equipment top to be made from 16 swg with all sides down bedded twice within ss angle/SS pipe support..All bottom and upper shelves to be made from 18swg with all sides down bedded twice within ss angle/ss pipe support. Side covers to be made from 18 swg. NO MILD STEEL TO BE USED ANY WHERE IN THE CONSTRUCTION. All shelves to have stiffner support. All equipment to be made on 1.5" dia. s.s. pipe with adjustable nylon bolt.

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:

The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No.25

SS table with 2 u/s with lockable door (1200x650x850+150) mm (MK-11): Supply, Installation and Commissioning of SS table with 2 u/s with lockable door which includes preparation of shop drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling and storage at site, final assembly at designated rooms at any floor level as per the Technical Specification.

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:

The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No.26

SS makeline with Undercounter fridge (GN pan 10Nos) (1800x650x850) mm (MK-12): Supply, Installation and Commissioning of SS Makeline with undercounter Fridge with GN pan 10 equipment which includes preparation of shop drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling and storage at site, final assembly at designated rooms at any floor level as per the Technical Specification. The top shall be made of 16 SWG SS 304 with 150mm high back splash. Interior frame structure to be made of SS 16 swg . 25mm or 30mm Square Pipe and additional frame support of SS 16 SWG. . All Legs to be made of SS 16 SWG . 40mm 304 quality Square Pipe with adjustable nylon bolts. All equipment top to be made from 16 swg with all sides down bedded twice within ss angle/SS pipe

support..All bottom and upper shelves to be made from 18swg with all sides down bedded twice within ss angle/ss pipe support. Side covers to be made from 18 swg. NO MILD STEEL TO BE USED ANY WHERE IN THE CONSTRUCTION. Compressor : Emerson make.

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:

The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No. 27

Wall shelf (1800x450) mm (MK-12A): Supply, Installation and Commissioning of SS Wall shelf equipment which includes preparation of shop drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling and storage at site, final assembly at designated rooms at any floor level as per the Technical Specification. : The top shall be made of 16 SWG SS 304 . Interior frame structure to be made of SS 16 swg . 25mm or 30mm Square Pipe and additional frame support of SS 16 SWG. All bottom and upper shelves to be made from 18swg with all sides down bedded twice within ss angle/ss pipe support. Side covers to be made from 18 swg.

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:

The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No.28

SS pizza oven stone base (26"x16"x10") (MK-13): Supply, Installation and Commissioning of SS Pizza oven stone base equipment which includes preparation of shop drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling and storage at site, final assembly at designated rooms at any floor level as per the Technical Specification. : The top shall be made of 16 SWG SS 304 . Interior frame structure to be made of SS 16 swg . 25mm or 30mm Square Pipe and additional frame support of SS 16 SWG. All Legs to be made of SS 16 SWG . 40mm 304 quality Square Pipe with adjustable nylon bolts. All equipment top

to be made from 16 swg with all sides down bedded twice within ss angle/SS pipe support..All bottom and upper shelves to be made from 18swg with all sides down bedded twice within ss angle/ss pipe support. Side covers to be made from 18 swg. NO MILD STEEL TO BE USED ANY WHERE IN THE CONSTRUCTION. Thermostate of good quality , Two Coil in a oven , Inner size of oven : 25"x15"x9", 4 Kw power.

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:

The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No.29

Sandwich Griller (Jumbo) (MK-14) : Supply, Installation and Commissioning of SS Sandwich griller Jumbo equipment which includes preparation of shop drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling and storage at site, final assembly at designated rooms at any floor level as per the Technical Specification. : The top shall be made of 16 SWG SS 304. Interior frame structure to be made of SS 16 swg . 25mm or 30mm Square Pipe and additional frame support of SS 16 SWG.. All equipment top to be made from 16 swg with all sides down bedded twice within ss angle/SS pipe support. All bottom and upper shelves to be made from 18swg with all sides down bedded twice within ss angle/ss pipe support. Side covers to be made from 18 swg. NO MILD STEEL TO BE USED ANY WHERE IN THE CONSTRUCTION. Thermostate of good quality , Size : 12x12 , 2.6 Kw 4 slice at a time.

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:

The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No.30

Electric Freyer 8 ltr (MK-15) : Supply, Installation and Commissioning of SS Deep fat fryer equipment which includes preparation of shop drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling and storage at site, final assembly at designated rooms at any floor level as per the

Technical Specification.: The top shall be made of 16 SWG SS 304. Interior frame structure to be made of SS 16 swg. 25mm or 30mm Square Pipe and additional frame support of SS 16 SWG.. All equipment top to be made from 16 swg with all sides down bedded twice within ss angle/SS pipe support. All bottom and upper shelves to be made from 18swg with all sides down bedded twice within ss angle/ss pipe support. Side covers to be made from 18 swg. NO MILD STEEL TO BE USED ANY WHERE IN THE CONSTRUCTION. Thermostate of good quality , Heater SS make , 2.5kw power.

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:

The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No. 31

Salamanadar (19"x12"x10") (MK-16): Supply, Installation and Commissioning of SS Salamadar equipment which includes preparation of shop drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling and storage at site, final assembly at designated rooms at any floor level as per the Technical Specification. : The top shall be made of 16 SWG SS 304 . Interior frame structure to be made of SS 16 swg . 25mm or 30mm Square Pipe and additional frame support of SS 16 SWG.. All equipment top to be made from 16 swg with all sides down bedded twice within ss angle/SS pipe support..All bottom and upper shelves to be made from 18swg with all sides down bedded twice within ss angle/ss pipe support. Side covers to be made from 18 swg.NO MILD STEEL TO BE USED ANY WHERE IN THE CONSTRUCTION. Thermostate of good quality , Size :19"x12"x10" inner , 3 kw power , one shelf (Jali) , fully ss body , two thermostat up and Down Temp.50 to 300 C.

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:

The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No. 32

SS table with 1 Undershelf (600x700x850+150) mm (TRS-01) : Supply, Installation

and Commissioning of SS Service table with 1 U/s equipment which includes preparation of shop drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling and storage at site, final assembly at designated rooms at any floor level as per the Technical Specification. : The top shall be made of 16 SWG SS 304 . Interior frame structure to be made of SS 16 swg . 25mm or 30mm Square Pipe and additional frame support of SS 16 SWG. . All Legs to be made of SS 16 SWG . 40mm 304 quality Square Pipe with adjustable nylon bolts.All equipment top to be made from 16 swg with all sides down bedded twice within ss angle/SS pipe support..All bottom and upper shelves to be made from 18swg with all sides down bedded twice within ss angle/ss pipe support. Side covers to be made from 18 swg. NO MILD STEEL TO BE USED ANY WHERE IN THE CONSTRUCTION. All shelves to have stiffner support. All equipment to be made on 1.5" dia. s.s. pipe with adjustable nylon bolt.

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:

The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No.33

SS Idli steamer with SS tray and stand (96 Pcs) (TRS-02): Supply, Installation and Commissioning of SS Idli Steamer With SS tray equipment which includes preparation of shop drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling and storage at site, final assembly at designated rooms at any floor level as per the Technical Specification. : The top shall be made of 16 SWG SS 304 . Interior frame structure to be made of SS 16 swg . 25mm or 30mm Square Pipe and additional frame support of SS 16 SWG. . All Legs to be made of SS 16 SWG . 40mm 304 quality Square Pipe with adjustable nylon bolts. All equipment top to be made from 16 swg with all sides down bedded twice within ss angle/SS pipe support..All bottom and upper shelves to be made from 18swg with all sides down bedded twice within ss angle/ss pipe support.Side covers to be made from 18 swg. NO MILD STEEL TO BE USED ANY WHERE IN THE CONSTRUCTION. All shelves to have stiffner support. All equipment to be made on 1.5" dia. s.s. pipe with adjustable nylon bolt. Tray capacity : 12 Nos , Tray Size : 14"x18", 8 tray, full ss body.

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:
The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No. 34
SS chapati plate with puffer with 1 Undershelf (1800x700x850+150) mm (TRS-03) : Supply, Installation and Commissioning of SS Dosa plate with 1 U/s which includes preparation of shop drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling and storage at site, final assembly at designated rooms at any floor level as per the Technical Specification. The top shall be made of 16 SWG SS 304 with 150mm high back splash. . All Legs to be made of SS 16 SWG . 40mm 304 quality Square Pipe with adjustable nylon bolts.All equipment top to be made from 16 swg with all sides down bedded twice within ss angle/SS pipe support..All bottom and upper shelves to be made from 18swg with all sides down bedded twice within ss angle/ss pipe support. Side covers to be made from 18 swg. NO MILD STEEL TO BE USED ANY WHERE IN THE CONSTRUCTION. All burners to be provided with ss spillage trays with s.s. handles. All burners and regulators to be sourced from ISI mark suppliers. R.V burner of good quality , capsule type puffer.

Mode of Measurements:
- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:
The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No. 35
SS Tilting type Boiling Pan (100 ltr) (TRS-04) : Supply, Installation and Commissioning of SS Tilting type Boiling Pan SS 304 grade material will be used for whole body , SS 304 14 SWG for boiling tank , 18 SWG for top lid of the boiling tank , 20 SWG for both side control box removable panel , 12 SWG for bottom of the tank , mechanism for lid will be spring loaded , SS 304 sq .tube 50mmx50mmx2mm thick for under construction frame work , GS-45 burner , pilot burner , needle control valve , copper pigtail etc. M.S tata 'c' class 22 mm pipe for mani fold, water faucet will be mounted on the R.H.S control box with 1/2"bsp 1 mtr water inlet flexible pipe. at any floor level as per the Technical Specification.

Mode of Measurements:
- The work must be completed as per drawings and instructions by EIC/Architect.

- The measurement shall be taken in **number**.

Rates:
The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No. 36
Soiled Dish Collecting table with garbage chute and dustbin 90 ltr capacity (1200x710x850+450) mm (DW-01) : Supply, Installation and Commissioning of Ss soiled Dish Landing table with Garbage Cute equipment which includes preparation of shop drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling and storage at site, final assembly at designated rooms at any floor level as per the Technical Specification. : The top shall be made of 16 SWG SS 304 . Interior frame structure to be made of SS 16 swg . 25mm or 30mm Square Pipe and additional frame support of SS 16 SWG. . All Legs to be made of SS 16 SWG . 40mm 304 quality Square Pipe with adjustable nylon bolts. All equipment top to be made from 16 swg with all sides down bedded twice within ss angle/SS pipe support..All bottom and upper shelves to be made from 18swg with all sides down bedded twice within ss angle/ss pipe support. Side covers to be made from 18 swg. NO MILD STEEL TO BE USED ANY WHERE IN THE CONSTRUCTION. All shelves to have stifner support. All equipment to be made on 1.5" dia. s.s. pipe with adjustable nylon bolt. Glass shelf also required for basket stacking .

Mode of Measurements:
- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:
The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No. 37
SS Two sink unit with back splash (1200x710x850+450) mm (DW-02) : Supply, Installation and Commissioning of SS two sink unit with back splash equipment which includes preparation of shop drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling and storage at site, final assembly at designated rooms at any floor level as per the Technical Specification. The top shall be made of 16 SWG SS 304 with 150mm high back splash. The Sink shall be of size 450mm x 450mm x450mmdeep made of 16 SWG SS 304. Interior frame structure to be made of SS 16 swg . 25mm or 30mm Square Pipe and additional frame support of SS 16 SWG. Uprights & Cross Bracing to be made of SS 16 SWG

.25mm Or 30MM Square Pipe 304 Quality . All Legs to be made of SS 16 SWG . 40mm 304 quality Square Pipe with adjustable nylon bolts. All equipment top to be made from 16 swg with all sides down bedded twice within ss angle/SS pipe support..All bottom and upper shelves to be made from 18swg with all sides down bedded twice within ss angle/ss pipe support. Side covers to be made from 18 swg. NO MILD STEEL TO BE USED ANY WHERE IN THE CONSTRUCTION.

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:

The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No.38

Pri Rinse Unit Deck Mounted (DW-02A): Supply, Installation and Commissioning of Pri Rinse Unit Deck Mounted equipment which includes preparation of shop drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling and storage at site, final assembly at designated rooms at any floor level as per the Technical Specification: Model No : EX-1DP00-H, Make: T & S (Imported) /Aluids/ Zephyr.

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:

The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No. 39

SS table (710x710x850+150) mm (DW-03): Supply, Installation and Commissioning of SS Service table with 1 U/s equipment which includes preparation of shop drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling and storage at site, final assembly at designated rooms at any floor level as per the Technical Specification.: The top shall be made of 16 SWG SS 304 . Interior frame structure to be made of SS 16 SWG. 25mm or 30mm Square Pipe and additional frame support of SS 16 SWG. All Legs to be made of SS 16 SWG. 40mm 304 quality Square Pipe with adjustable nylon bolts. All equipment top to be made from 16 SWG with all sides down bedded twice within SS angle/SS pipe support. All bottom

and upper shelves to be made from 18swg with all sides down bedded twice within SS angle/SS pipe support. Side covers to be made from 18 SWG. NO MILD STEEL TO BE USED ANY WHERE IN THE CONSTRUCTION. All shelves to have stiffner support. All equipment to be made on 1.5" dia. S.S. pipe with adjustable nylon bolt.

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:

The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No.40

Hood Type Dishwasher Machine (60 Racks Winterhalter) (DW-04): Supply, Installation and Commissioning of Hood Type Dishwasher P-50- Winter Halter make equipment which includes preparation of shop drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling and storage at site, final assembly at designated rooms at any floor level as per the Technical Specification : Make: Winterhalter / Hobert / Electrolux.

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:

The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No. 41

SS clean Dish Landing table with SS angle below for Basket storage (1000x720x850) mm (DW-05): Supply, Installation and Commissioning of SS Clean Dish Landing table equipment which includes preparation of shop drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling and storage at site, final assembly at designated rooms at any floor level as per the Technical Specification.: The top shall be made of 16 SWG SS 304. Interior frame structure to be made of SS 16 SWG . 25mm or 30mm Square Pipe and additional frame support of SS 16 SWG. All Legs to be made of SS 16 SWG . 40mm 304 quality Square Pipe with adjustable nylon bolts. All equipment top to be made from 16 SWG with all sides down bedded twice within SS angle/SS pipe support. All bottom and upper shelves to be made from 18swg with all sides down bedded twice within SS angle/SS pipe support. Side

covers to be made from 18 SWG. NO MILD STEEL TO BE USED ANY WHERE IN THE CONSTRUCTION. All shelves to have stiffner support. All equipment to be made on 1.5" dia. S.S. pipe with adjustable nylon bolt.

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:

The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No.42

SS Dish Rack with four shelf (1350x500x1800) mm (DW-06) : Supply, Installation and Commissioning of SS Storage Rack Perforated 1350x500x1800 Rack with Four Shelf equipment which includes preparation of shop drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling and storage at site, final assembly at designated rooms at any floor level as per the Technical Specification. : The top shall be made of 16 SWG SS 304. Interior frame structure to be made of SS 16 SWG. 25mm or 30mm Square Pipe and additional frame support of SS 16 SWG. All Legs to be made of SS 16 SWG . 40mm 304 quality Square Pipe with adjustable nylon bolts. All equipment top to be made from 16 SWG with all sides down bedded twice within SS angle/SS pipe support. All bottom and upper shelves to be made from 18 SWG with all sides down bedded twice within SS angle/SS pipe support. Side covers to be made from 18 SWG. NO MILD STEEL TO BE USED ANY WHERE IN THE CONSTRUCTION. All shelves to have stiffner support. All equipment to be made on 1.5" dia. S.S. pipe with adjustable nylon bolt.

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:

The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No. 43

Horizontal Geyser (100 ltr) (PW-02) : Supply, Installation and Commissioning of HORIZONTAL GEYSER - 100 LTR which includes preparation of shop drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling and storage at site, final assembly at designated rooms at any floor

level as per the Technical Specification. : 3000 watt , Water Pressure 8 BAR , Corded Electric. Make: AO Smith / Racold / Havells.

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:

The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No. 44

Pot rack with three shelf (1350x500x1800) mm (PW-03): Supply, Installation and Commissioning of SS Pot rack with Three Shelf equipment which includes preparation of shop drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling and storage at site, final assembly at designated rooms at any floor level as per the Technical Specification.: The top shall be made of 16 SWG SS 304. All Legs to be made of SS 16 SWG . 40mm 304 quality Square Pipe with adjustable nylon bolts. All equipment top to be made from 16 SWG with all sides down bedded twice within SS angle/SS pipe support. All bottom and upper shelves to be made from 18 SWG with all sides down bedded twice within SS angle/SS pipe support. NO MILD STEEL TO BE USED ANY WHERE IN THE CONSTRUCTION. All equipment to be made on 1.5" dia. S.S. pipe with adjustable nylon Bullet feet.

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:

The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No. 45

HOSEREEL - 5HR -232-01 (SC-01): Supply, Installation and Commissioning of Hose reel equipment which includes preparation of shop drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling and storage at site, final assembly at designated rooms at any floor level as per the Technical Specification : Model No : 5HR-232-01 , Make: T & S (Imported) / Aluids / Zephyr.

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:
The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No. 46
SS service table with 1under shelf , 3 side covered. (1300x650x850) mm (SC-02) : Supply, Installation and Commissioning of SS service table with 1under shelf tray railing with sneez gaued , 3 side covered equipment which includes preparation of shop drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling and storage at site, final assembly at designated rooms at any floor level as per the Technical Specification. : The top shall be made of 16 SWG SS 304 . Interior frame structure to be made of SS 16 SWG. 25mm or 30mm Square Pipe and additional frame support of SS 16 SWG. All Legs to be made of SS 16 SWG . 40mm 304 quality Square Pipe with adjustable nylon bolts. All equipment top to be made from 16 SWG with all sides down bedded twice within SS angle/SS pipe support. All bottom and upper shelves to be made from 18swg with all sides down bedded twice within SS angle/SS pipe support. Side covers to be made from 18 SWG. NO MILD STEEL TO BE USED ANY WHERE IN THE CONSTRUCTION. All shelves to have stiffner support. All equipment to be made on 1.5" dia. S.S. pipe with adjustable nylon bolt.

Mode of Measurements:
- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:
The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No.47
SS baine marie with 1/1-150 6 Nos GN pan , both side Tray Railing , sneez Gaurd , three side covered (2300x650x850+450+300) mm (SC-03) : Supply, Installation and Commissioning of SS baine marie with 1/1-150 6 Nos GN pan , Tray Railing , sneez Gaurd, three side covered equipment which includes preparation of shop drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling and storage at site, final assembly at designated rooms at any floor level as per the Technical Specification. : The top shall be made of 16 SWG SS 304 . Interior frame structure to be made of SS 16 SWG. 25mm or 30mm Square Pipe and

additional frame support of SS 16 SWG. All Legs to be made of SS 16 SWG. 40mm 304 quality Square Pipe with adjustable nylon bolts. All equipment top to be made from 16 SWG with all sides down bedded twice within SS angle/SS pipe support. All bottom and upper shelves to be made from 18swg with all sides down bedded twice within SS angle/SS pipe support. Side covers to be made from 18 SWG. NO MILD STEEL TO BE USED ANY WHERE IN THE CONSTRUCTION. All shelves to have stiffner support. All equipment to be made on 1.5" dia. S.S. pipe with adjustable nylon bolt. GN pan ZANUFF/Nilkamal /ANUPAM MAKE.

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:

The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No.48

SS service table with 1under shelf , 3 side covered (1000x650x850) mm (SC-04) : Supply, Installation and Commissioning SS service table with 1under shelf , 3 side covered which includes preparation of shop drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling and storage at site, final assembly at designated rooms at any floor level as per the Technical Specification.

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:

The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No.49

Visi Cooler (280 ltr) western or same (700x700) mm (SC-05): Supply, Installation and Commissioning of VIsi Cooler - 280 ltr equipment which includes preparation of shop drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling and storage at site, final assembly at designated rooms at any floor level as per the Technical Specification. : VISI COOLER - WESTERN MAKE - 280 LTR- SRC 280GL/voltas / bluestar.

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:

The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No. 50

Water Cooler 150 ltr (HW-02) : Supply, Installation and Commissioning of SS water cooler 150 ltr- 2 QTY with RO equipment which includes preparation of shop drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling and storage at site, final assembly at designated rooms at any floor level as per the Technical Specification. : The top shall be made of 16 SWG SS 304. Interior frame structure to be made of SS 16 SWG. 25mm or 30mm Square Pipe and additional frame support of SS 16 SWG. All equipment top to be made from 16 SWG with all sides down bedded twice within SS angle/SS pipe support. All bottom and upper shelves to be made from 18swg with all sides down bedded twice within SS angle/SS pipe support. Side covers to be made from 18 SWG. NO MILD STEEL TO BE USED ANY WHERE IN THE CONSTRUCTION. All shelves to have stiffner support. All equipment to be made on 1.5" dia. S.S. pipe with adjustable nylon bolt. Emesron Make Compressor. Material: water cooler 150 ltr- 2 QTY with RO. Make: Voltas / Bluestar.

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:

The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No.51

SS service table (1500x600x850+150) mm (VP-02): Supply, Installation and Commissioning of SS service table with 2 Under shelf 3 side covered equipment which includes preparation of shop drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling and storage at site, final assembly at designated rooms at any floor level as per the Technical Specification.: The top shall be made of 16 SWG SS 304. Interior frame structure to be made of SS 16 SWG . 25mm or 30mm Square Pipe and additional frame support of SS 16 SWG. All Legs to be made of SS 16 SWG . 40mm 304 quality Square Pipe with adjustable nylon bolts. All equipment top to be made from 16 SWG with all sides down bedded

twice within SS angle/SS pipe support. All bottom and upper shelves to be made from 18 SWG with all sides down bedded twice within SS angle/SS pipe support. Side covers to be made from 18 swg. NO MILD STEEL TO BE USED ANY WHERE IN THE CONSTRUCTION. All shelves to have stiffner support. All equipment to be made on 1.5" dia. S.S. pipe with adjustable nylon bolt.

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:

The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No. 52

Induction plate with chaffer (6 Nos) (VP-03): Supply, Installation and Commissioning of which includes preparation of shop drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling and storage at site, final assembly at designated rooms at any floor level as per the Technical Specification. : Cheffo make induction chaffer model no : AG6006 , 6 ltr. capapcity round type, induction make: cheffo code : ciut2000wt , size: 350x350x110 mm , 2000w capacity. Make: Cheefo / Cuba / Stella.

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:

The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No.53

Platform Trolley (750x500x860) mm : Supply, Installation and Commissioning of SS Platform trolley equipment which includes preparation of shop drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling and storage at site, final assembly at designated rooms at any floor level as per the Technical Specification. : The top shall be made of 16 SWG SS 304. Interior frame structure to be made of SS 16 SWG. 25mm or 30mm Square Pipe and additional frame support of SS 16 SWG. All equipment top to be made from 16 SWG with all sides down bedded twice within ss angle/SS pipe support. All bottom and upper shelves to be made from 18 SWG with all sides down bedded twice within SS angle/SS

pipe support. Side covers to be made from 18 SWG. NO MILD STEEL TO BE USED ANY WHERE IN THE CONSTRUCTION. All shelves to have stiffner support. All equipment to be made on 1.5" dia. S.S. pipe with adjustable nylon bolt.wheels -4 nos.

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:

The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No.54

Utility trolley with 2 u/s (STD) : Supply, Installation and Commissioning of SS Utility Trolley with 2 u/s equipment which includes preparation of shop drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling and storage at site, final assembly at designated rooms at any floor level as per the Technical Specification. : The top shall be made of 16 SWG SS 304 . Interior frame structure to be made of SS 16 SWG . 25mm or 30mm Square Pipe and additional frame support of SS 16 SWG. All equipment top to be made from 16 SWG with all sides down bedded twice within SS angle/SS pipe support. All bottom and upper shelves to be made from 18swg with all sides down bedded twice within SS angle/SS pipe support. Side covers to be made from 18 swg. NO MILD STEEL TO BE USED ANY WHERE IN THE CONSTRUCTION. All shelves to have stiffner support. All equipment to be made on 1.5" dia. S.S. pipe with adjustable nylon bolt. wheels -4 nos.

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:

The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No.55

SS Drain Grating 3 layer (900x300) mm : Supply, Installation and Commissioning of SS Drain Grating 3 layer which includes preparation of shop drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling and storage at site, final assembly at designated rooms at any floor level as per the Technical Specification.

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:

The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No.56

SS Soiled Dish Trolley with loose basket (900x600x850) mm : Supply, Installation and Commissioning of SS Soiled Dish Trolley with loose basket (900x600x850) which includes preparation of shop drawings, supply, packing & forwarding, delivery to site, including transit insurance arrangement, unloading, handling and storage at site, final assembly at designated rooms at any floor level as per the Technical Specification.

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:

The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No.57

SS 304 Exhaust Hood 18 SWG grade on all sides. Unit shall be of totally nut bolted construction without any Welding joints , Baffle type filter 22 swg . V section , with Lights CFL bulbs , Grease troughs should be Provided for each Sectional Piece. (1200x900x500) mm for tilting bratt pan (EX-01)

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:

The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No.58

SS 304 Exhaust Hood 18 SWG grade on all sides. Unit shall be of totally nut bolted construction without any Welding joints , Baffle type filter 22 swg . V section , with

Lights CFL bulbs , Grease troughs should be Provided for each Sectional Piece. (1200x900x500) mm for two burner and chinese gas range. (EX-02)

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:

The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No.59

SS 304 Exhaust Hood 18 SWG grade on all sides. Unit shall be of totally nut bolted construction without any Welding joints , Baffle type filter 22 swg . V section , with Lights CFL bulbs , Grease troughs should be Provided for each Sectional Piece. (1800x900x500) mm for chapati plate with puffer (EX-03)

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:

The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.

Item No.60

SS 304 Exhaust Hood 18 SWG grade on all sides. Unit shall be of totally nut bolted construction without any Welding joints , Baffle type filter 22 swg . V section , with Lights CFL bulbs , Grease troughs should be Provided for each Sectional Piece. (2100x900x500) mm for tilting boiling pan (EX-04).

Mode of Measurements:

- The work must be completed as per drawings and instructions by EIC/Architect.
- The measurement shall be taken in **number**.

Rates:

The rates for the item shall be include the cost of all the material, tools, and labor, involved in all the operations described above including cartage and lifts at all levels no additional payment for wastage.