BILLS OF QUANTITIES FOR INTERIOR FURNISHING WORK OF BANK OF BARODA FOR KHARGATE BRANCH, DIST. BHAVNAGAR

SEALED PRICE BID

Sr. No.	Description	Quantity	Rate	Unit	Amount
Note :	**Rate should be inclusive of material, labour, tools, machinary, scaffolding, final disposal of debris, cleaning cutting wastage etc. All taxes, transportation, VAT, Excise, Octroi etc. Excluding GST. Note: GST will be paid extra. As per Applicable norms**				
	List of Materials Used				
(i)	**Table Top/sides/Partition and Other surface-1.00 mm thick Laminate of AICA Sunmica No. SF499/1499 Frosty White or Equivelent and SF599/1599 Orange or Eqivelent.**				
[A]	**FURNISHING WORK**				
1	**P/F BOTH SIDE LAMINATE SOLID / PARTLY GLAZED FULL HEIGHT PARTITION WITH FLUSH DOOR SHUTTER [FOR MANAGER & OTHER CABINS]** Providing and fixing both sides laminate full height partly glazed partition using 50mm x 25mm x 1.50mm thick Aluminium members in a maximum grid of 600mm x 600mm **fixing 12 mm thick Plywood Board** on both sides **with 1.0 mm laminate** of approved make shall be fixed on plywood. Providing and fixing 5.0/8.0 mm thick float glass as directed in the partition. Providing and fixing door shutter using 32 mm thick flush shutter both side laminated and fixing 6 mm thick glass with beading patti, 5" Long 3 Nos stainless steel hinges, doorstop shall be provided as directed. Godrej Mortice lock shall be provided in door shutter. All visible members if not laminated shall have lacquer polished as directed. The partition shall be secured by fixing & extending the vertical members of the frame at critical points upto the bottom of the RCC Slab or sides/bottom of RCC beams & bottom horizontal member of frame shall be secured & fixed with the flooring as directed. **Measurement -Length x Height (One Side Only)** Partition height from floor level to bottom of flase ceiling of partition considered For purpose of payment partition height up to bottom of false ceilling only shall be measured and paid . No extra payment shall be made for members going up to slab/beam bottom	95		SMT	
1[a]	**LOW HEIGHT PARTITION : Same as item No-1 but Providing and fixing 12mm thk commercial plywood on both side with 1.0 mm thick laminate low height partition**	3		SMT	

Sr. No.	Description	Quantity	Rate	Unit	Amount
	Providing and fixing low height patition using 50mm x 25mm x 1.20mm thick Aluminium members maximum in grid of 2'-0" x 2'-0" fixing 12 mm thick commercial plywood of approved brand on both side of T.W skeleton and fixing **1.0 mm thick laminate** of approved shed on both sides. Fixing T.W member of 2.5" x 1" Steam Beach. members in a shape as directed shall be fixed on all exposed edges. Fixing 12mm thk free glass as directed. Applying polish on exposed steam beach members with polished edges as directed complete. **Measurement - Length x Height (One Side Only)** Partition height from floor level to top of partition considered.				
1[b]	Providing and fixing "Dorma/ Ozone/Godrej" or equivalent make door closure.	10		NO	
1[c]	**Providing and Fixing Slidding folding door shutter for Between Manager Cabin & Lounge as follows** Heavy duty slidding channel shall be fixed at top and a guiding channel shall be provided at bottom. Special revolving and rolling fixture shall be fixed at top guiding rod shall be providing at bottom and total 4 no SS hinges shall be provided in one shutter. All hardware must be got approved from Architect before installing. Shutters shall be made using 25x50x1.5mm thick Aluminium members for frame work as per design with **12 mm thick Plywood Board with 1.00 mm thk laminate** of approved make on both faces. Providing 12 mm thick T.W beading all around shutter etc complete as directed and entire door shall have polish to the satisfaction of Architect. **Mechanism i.e sliding channel hinges, floor guide for slidding folding of "HUSH or Dorma" Company** **For purpose of payment Sliding folding door shutter height up to bottom of false ceilling only shall be measured and paid. No extra payment shall be made for members, ply wood going up to slab/beam bottom**	8		SMT	
2	**Providing and fixing Wicket Gate door with both side laminate** Providing and fixing 100 mm x 50 mm steam beach member for frame and flush door shutter made out of 31mm th wicket gate door shutter with both side 1.0mm thick laminate including SS hinges with countersunk SS screws, magnet, SS handle door stopper & polishing to exposed edges directed complete.	2		SMT	
2[a]	**Providing and fixing Flush door B/h Cash cabin Passage** Using 4" x 2" Steam beach members and 31mm th flush shutter with 5mm th glass vision panel as per design and instruction. Providing Steam beach member on periphery for fixing 4" long hinges 3 Nos. Fixing 1.0mm th laminate on both sides. Providing S.S Handles, Godrej Nigth latch Lock, stoppers, doorstop & polishing to exposed edges directed complete.	2		SMT	

Sr. No.	Description	Quantity	Rate	Unit	Amount
2[b]	**Providing and fixing Isolated flush door shutter (Partly Glazed and Partly Laminate) with frame as follows.** Using 4" x 2" Steam beach members and 31mm th flush shutter with 5mm th glass vision panel as per design and instruction. Providing Steam beach member on periphery for fixing 4" long hinges 3 Nos. Fixing 1.0mm th laminate on both sides. Providing S.S Handles, Godrej Mortice Lock, stoppers, doorstop & polishing to exposed edges directed complete.	6		SMT	
3	**Providing and fixing panelling on columns and above front side glass** Providing and laying pannelling on walls & pillers having 12 mm thk Commericla Plywood of Approved make and **1.0 mm thk laminate** fixed on wall & pillers with aluminium framing of 25mm x 25 mm x 1.20 mm thick at maximum 2'-0" c/c bothways or 18 mm thick plywood with laminate panelling on wall and piller and creating box above main door and fixed glass partition etc complete as directed. pannelling as per design and instruction of Architect.	85		SMT	
4	**P & F LOW / FULL HEIGHT STORAGE UNITS** **Detailed Specification:** Depth 406mm (1'-4") Height 760mm (2'-6") / 914mm (3'-0") / 2134mm (7'-0") height having openable shutter as directed. Cabinet shall be made from 18mm thick ply wood for verticale shelves, shutter and 8mm th plywood for backing with 1.0 mm thick laminate on all exposed surface (Laminate on Low height SCB exposed back side) and balacing laminate for all internal surface with verticale (at 914mm/3'-0"c/c) shelves at 381mm (1'-3") shutter openable shutters in 18 mm thick Ply wood with all S.S Auto hinges, tower bolts power coated handle ball catches, S.S (group lock) multi purpose lock completed Edges to be finshed with teak wood lipping with polishing etc. including all incidental surface to be polished/painted etc. complete, all the Non visible surface shall be have 0.60 mm thick balancing laminate of approved shed as directed. **Cabinate shall be measured as (Length x Height) for the purpose of payment)**	9		SMT	

Sr. No.	Description	Quantity	Rate	Unit	Amount
4[a]	**Providing and fixing Pantry plateform shutter with 3 Nos Basket Drawers** Detailed Specification: Providing and fixing cupboard shutters with 3 nos Baskets below pantry platform using 1 1/2" x 2 1/2" Teak Wood members for frame, 18mm Thick Commercial plywood with 1.0 mm thick laminate on all exposed surface and all internal surfaces shall have balancing laminate for shutters. Providing 1/2" thick Teak Wood beading all around shutter. Providing S.S hinges, Handles, Stoppers and magnetic catch, S.S tray/baskets of S.S grade 304 of Ever shine make or approved equivalent Viz 1 No of plain Basket, 1 No of Cutlery Basket (Perforated) of size 15"x20"x4" and 1 No of thali Basket of size 15"x20"x8" in each of two storage spaces i.e total 3 baskets in plan area of approx. 0.60 sqmt. Baskets should be fitted over heavy dutty telescopic channels,S.S handles and other necessary hardwares as instructed at site. Providing 2 mm thick PVC beading all around drawer front side edges, etc. As per design & instruction of Architect. **Measurement - Pantry Platform shutter outer Length x Height.**	1		SMT	
5	**Providing soft board for pin up** **Detailed Specification:** using T.W frame of 1" x 1/2" with 8mm thick commercial plywood on back side and 12mm th soft board on front. Fixing cloth of selected design of Basic rate of Rs. 150 per mt. soft board fixed with SS Stud as directed complete. **Measurement - Length x Height.**	1		SMT	
6	CUSTOMER WRITING DESK 3'-0"x1'-3"x 0'-6" **Detailed Specification:** Verticale Sides and bottom shall be made from 18mm th Commercial plywood with 1.0 mm thick lamiante on all sides including inside divisions. Top shall be made from 12mm th glass with bevelled and polished edges making diff divisions by 8mm th glass for slips or forms as per detail drawing directed complete.	1		NO	
6[a]	Providing and fixing of letter box cum suggestion box of size 3' 0"x1'-3" x 3'-0" ht. **Detailed Specification:** Box shall be made from 18mm thick commercial ply wood with 1.0mm thick laminate, back shall be 8mm th commercial plywood shutter shall be made from 18mm thick commercial ply woodwith 1.0mm thick laminate and lock, The top shall have a slit for dropping latter, all the surface of the box without laminate shall have polish as directed.	1		NO	
7	Supplying and fixing Roller Blind Blackout of approved make with selected fabric of approved design and shade. **Measurement - Length x Height.**	10		SMT	

Sr. No.	Description	Quantity	Rate	Unit	Amount
8	**ALUMINUM COMPOSITE PANEL FOR FRONT SIDE ELEVATION** **Detailed Specification:** Providing and fixing 3 mm thick aluminium composite panel with 0.25 mm foil with 2" x 1" x 1.60 mm thick aluminium hollow section tray system with minimum 20 mm bending with silicon Dow Coming of GE seal proof - complete as per selection and direction of Architect. This item will be carried out as per manufacturer specifications Rate includes trap door shutters. **Measurement: Only finished surface area shall be measured for payment. Length x Height**	35		SMT	
	DOORS				
9	**MAIN DOOR (Approx Size 3'-0'/4'-0" X 7'-0") Openable Glass door shutter with Patch Fitting** Providing & Fixing fully glazed main door at the main entrance The Item includes fixing of **12 mm th. Toughned glass** with the help of **top patch & bottom patch fittings.** The door will have patch lock, pti pivot, floor spring & 600 mm long handles, fixed with the glass by making necessary cutouts & holes. The glass edges shall be polish on all sides. The entire door shall be errected in complete line & level. The door will have S.S brush finish Signage for pull & push.The entire door, complete in all respect should be installed in positions as req. **Measurement - Length x Height.**				
[a]	[I] OPENABLE PORTION Glass Door with Patch Fitting	7		SMT	
10	FRONT Glazing Partition: Fixed Portion partition With Patch Fitting Same as Item No. 9, FRONT Glazing Partition: Providing and fixing of fully glazed partion with 12mm thick toughned glass fitted with heavy duty SS patch fittings at the interval of minimum 2'-0" interval at top, bottom and sides as per site condition.	16		SMT	
	FALSE CEILLING				
11	Providing and fixing Gypsum board 12.50 mm thick false ceiling in steps and design using Original Indian Gypsum board with original GI sheet section **of Gypsteel (Gypsteel shall be used)** supporting system in line and level. Finishing the surface and **applying 3 coats of Plastic emulsion paint** as directed complete. Entire work to be done as per standard specifications of Saint Gobin Gyproc India.. **Note : (1) Rate includes making necessary cutouts for lighting fixtures (2) Only finished visible surface area shall be measured for payment. (3) Cutout for light and Diffusers / grill will not be deducted from area for payment purpose. (4) Pattas if any shall be measured in SqM and not in RMt and paid in SqM .** **Mode of Measurements:- Finished visible surface area shall be measured and Paid.**	175		SMT	

Sr. No.	Description	Quantity	Rate	Unit	Amount
12	Providing and fixing of Armstrong Mineral Fibre Acoustical Suspended Ceiling System with 16 mm thick FINE FISSURED (MICRO LOOK) EDGE TILES WITH ARMSTRONG SELECT (Black Reveal) 15 mm EXPOSED GRID. Using Select Grid with Fine Fissured (microlook) With necessary Angles at junctions as per company specifications as directed complete. Rate includes necessary cut outs for A/C Grills, diffusers light fixtures complete as directed. **Cutout for lighting fixture and Diffusers will not be deducted from area for payment purpose.** **Mode of Measurements:- Only plan area shall be measured and Paid. Length X width**	105		SMT	
13	**Supplying and providing 600 mm x 600 mm Center Tea poy as follows.** Providing and making Teapoy using 12mm thick thoughened Glass with bevelled and polishing edges on top of glass. Supported on SS studs as shown in drawing 18 mm thick plywood with 1.0 mm thick laminate shall be used to make box for suppoting SS studs complete as directed.	3		NO	
	LOOSE FURNITURE WORK [CASH COUNTER & TABLES/SIDE TABLES				
14	**CASH COUNTER SIZE L 5'-0" X W 2'-3"/6" x 3 Ht 3'-9" WITH Rate Including Front side 12 mm thick Toughend Glass Partition above Transaction Top (3'-0" to 3'-6"Height)** Supplying, fixing and keeping in position single window counter complete as per design, and drawing made out of 18mm thick commercial ply wood of approved make, complete with 19 mm. C.P. Teak wood lipping on all edges wherever required. The cost shall be inclusive of S & F of a drawer and shelf unit with 18mm thick commercial plywood and with **Godrej multipurpase Auto Lock** in drawer and shelf unit. The cost shall also be inclusive of the following.	2		NO	
[a]	size : Description: L B Ht. Writing Top 5'-0" 2'-9" 2'-6" Transaction Top 5'-0" 1'-9"/1'-0" 3'-9" 3 Drawers with pegion hole 2'-0" 1'-3" 2'-0" Computer key Board Supplying and fixing metal key Board of Ebco Earl Bihari make in counter as per design and instructions.				
[b]	Working top shall be finished with laminated sheet 1.0 mm thick of approved make, natural Teak wood Texture / choice shade laid with grains parallel to the length of the counter.				
[c]	Transaction top finish as in (b) above.				
[d]	Front pannel and front projection shall be finished with laminated sheet 1.0 mm thick of choice shade approved by Architects/Bank and fixed on 18 mm thick commercial ply wood with horizontal and vertical grooves as per design.				

Sr. No.	Description	Quantity	Rate	Unit	Amount
[e]	Orage bend : 5.75" (145mm) high Laminated sheet 1.0mm thick for bend shall be glued on to pannel of [in front] 18 mm thick commercial ply wood of approved make ht.				
[f]	The projecting portion shall have 9" deep with vertical supports as requored made of 18mm thick commercial ply wood of approved make.				
[g]	Foot rest of 3" x 1.5" in C.P. Teak wood. and CPU stand 18" x 24"				
[h]	All wood work shall be laquer polished to a smooth and uniform finish of choice colour and shade.				
[i]	All fittings like S.S. handle/ Godrej/**EG make Auto Lock** to each drawer and cabinet doors, piano hinges, ball catcher stopper, metal cable manager etc. Ebco make heavy duty full extention channel in drawers.				
[j]	**Heavy duty telescope fullextantion slidding channel of Ebco make or equ. make shall be used in all drawers.**				
[k]	**All the Non visible surface shall be have 0.60 mm thick balancing laminate of approved shed**				
[l]	**Providing and fixing thoughned Glass partition on counter front side top as follows** Providing and fixing 12 mm thick thoughned glass with bevelled and polished edges shall be fixed with necessary S.S Brush finish brackets support on wooden partition as directed Making necessary cut out in glass all edges of glass shall be Diamond cut polished edges as directed complete.				
[m]	**Counter shall be made independent in Length of 4'-6" and properly placed between two partition. Same as Moduler Type (Drawing as enclosed herewith)**				
14[a]	**Providing & fixing Low height partition For CASH CABIN including Flush door shutter & 12mm thick Toughened Glass** Providing and fixing low height patition using 50mmx25mmx1.20mm thick Aluminium members maximum in grid of 2'-0" x 2'-0" fixing **12 mm thick commercial plywood** of approved brand on both side of Aluminium skeleton and fixing 1.0 mm thick laminate of approved shed on both sides. Fixing T.W member of 2.5" x 1 " Steam Beach. members in a shape as directed shall be fixed on all exposed edges. **P & Fixing 12mm th free Toughened glass as directed.** Applying polish on exposed steam beach members with polished edges as directed complete. Rate including Providing and fixing 31mm th Flush door shutter with both side 1.0mm thick laminate as per design and instruction. Providing Steam beach member on periphery for fixing 4" long hinges 3 Nos. Providing S.S Handles, Night latch Lock, stopper & polishing to exposed edges directed complete.	18		SMT	

Sr. No.	Description	Quantity	Rate	Unit	Amount
	TABLES				
15	MANAGER TABLE SIZE: 6'-0" X 2'-9" X2'-6" HT. with Laminate finish on Table Top, sides and all other visible surfaces etc complete as follows Supplying and installation of Table as per the following description: Size 7'-0" x 3'-0". Table top shall be made from 18 mm thick commercial ply wood with 1.0 mm thick Laminate with necessary intermediate support. Table top shall be supported by 18 mm thick commercial ply wood with wooden framing. Storage cabinet of 1'-3" x 2'-0" x 2'-6" shall be provided using 18 mm thick commercial ply wood having 4 Nos drawers as directed with heavy duty telescope sliding channel of approved make , grouplock, S.S. Handle. Computer Key board of metal of approved make shall be provided. Exposed surfaces of the CABINET shall have laminate, Foot rest of 1 1/2" x 3" T.W members shall be provided. All internal surface will have 0.60 mm thick balacing laminate Apron (Modesty Panel) made from 18 mm thick ply wood finished with laminate as per drawing Table side made from 18 mm thick ply wood with 1.0 mm thick Laminate finish shall be provided in a pattern as per drawing. Laminate to be provided on all visible surfaces. Drawer Fascia made out of 18 mm thick Plywood. The sides/back/base of drawers be made of 12 mm thick Ply wood & Bottom of drawers shall be of 6 mm thick ply wood. fixing laminate on front side and all the internal surfaces shall be 0.60 mm thick balancing laminate. The drawers to be fitted with Telescopic sliding channel with SS Group locks of approved make and 100 mm long brush finish Stainless Steel handles for each drawer. All the edges of Drawer Fascia be provided with teak wood edge bending with laqucer polished etc complete as directed. Table shall have stand for keeping CPU and metalic cable Manager shall be provided in table top. All exposed edges of teak wood shall have polished with smooth edges & corners Exposed edges of Table Top, Leg panel & Side Shelf shall be made 36 mm thick by providing additional 18 mm thick ply wood patta of required width. All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate of approved shade. Etc. complete. All the surface without laminate / balancing laminate shall be lacquered polished of approved shade As per drawing and instruction of Architect/Bank work to be Completed. FINISHING DETAILS IN NUTSHELL: **1) Table Top :** 1.0 mm thick Dark laminat**e** & Burma Teak beading on Edges with polished 2) **Front Appron & Sides:** 1.0 mm thick Dark Laminate 3) **Facing of Drawers:** 1.0 mm thick Dark Laminate 4) All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate **Note: Rate includes Foot rest and CPU Trolly with castors**	1		NO	

Sr. No.	Description	Quantity	Rate	Unit	Amount
15[a]	Same as above Item-no- 18, but Size: **5'-0"x2'-6"** with 4 Nos Drawer Unit with 1.0 mm thick Laminate finish on all exposed surfaces. (For Officer at GF, Advance Section & FOREX Dept.)	8		NO	
15[b]	Same as above item no- 18, but Size: **4'-3"x2'-0"** without Drawer Unit with 1.0 mm thick Laminate finished on all exposed surfaces. (For Officers)	4		NO	
15[c]	Same as above item no- 18, but Size: **4'-0"x2'-0"** without Drawer Unit with 1.0 mm thick Laminate finished on all exposed surfaces. (For Officers)	3		NO	
	SIDE CREDENZA (SIDE TABLE)				
16	**Side Credenza Size 3'-0"/ 3'-3"x1'-4" x 2'-6" ht. Openable shutter with 1.00 mm thick Laminate finish on Top , front, sides, shutter and 35 mmx6 mm thick Burma Teak beading on Top Edges. Laminate to be provided only on visible surface etc complete as follows. Only Front elevation will be measured for payment purpose. Rate for length Less then 3'-3"** Supplying and installation side cabinet for keeping computer and printer of size 1'-4" width 2'-6" height and 3'-6" length having openable shutters as directed. Cabinet shall be made from 18 mm thick commercial ply wood with 1.00 mm thick Laminate Finish. Back shall be made from 6 mm thick commercial plywood. Openable shutters shall be made from 18 mm thick commercial ply wood with laminate finished and approved make group lock, handle, hinges, magnet catch. , Rate includes all necessary provisions for installing computers. All the internal surface, back side shall have 0.60 mm thick balacing laminate Exposed edges of Sides, Table Top shall be made 36 mm thick by providing additional 18 mm thick ply wood patta of required width. All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate **FINISHING DETAILS IN NUTSHELL:** 1) Top : Dark Laminate & Burma Teak beading on Edges with pilishade 2) Front Appron & Sides: Frosty White Laminate	7		SMT	
16[a]	**SIDE CREDENZA (SIDE TABLE) with partly Drawers Same as above Item No 19 all external surfaces to be finished with 1.0 mm thick Laminate (approved shades). Size shall be 3'-0"/3'-3" x 1'-4" x 2'-6" ht. with Partly drawers & Partly openable shutters as directed** **FINISHING DETAILS IN NUTSHELL:** 1) Top : Dark Laminate & Burma Teak beading on Edges with pilishade 2) Front Appron & Sides: Frosty White Laminate	0		SMT	

Sr. No.	Description	Quantity	Rate	Unit	Amount
17	Providing and Installing MS Fabrication as per design for providing stair for going to Mezzenine Floor; with provision to install Seasoned Pine Wood steps complete as directed.	155		KG	
18	Providing and Fixing Seasoned Pine Wood steps on febricated stair complete as directed.	5		SMT	
19	**P/F S. S. RAILING** Providing Fabricating and installing in position S.S.railing (304 grade min.wall thickness 2mm) on entrance step/Ramp etc. as per the given design.The height of the railing shall be 1000 mm from the respective finished floor level. a) 40 mm dia S.S. (medium) pipe as main vertical & top hand rails members as per the given design .Incl tint, welding, grinding, finishing, hydralically bending etc **Rate including M 20 Concrete embedding 250x250x 600 mm Height for SS Pipe** b) 3 Nos 19mm dia S.S. pipes (medium) at Horizontal as intermediate supports verticale at given distances and as intermediate vertical members at a distance not more than 0.92 mtr. Note: Some changes in drawing may be necessary as per available chain and pipes which shall be got approvaed from Bank/Architect before execution	10		RMT	
20	**SS GRAB BAR** Supplying and installing 40 mm dia SS pipe 304 grade with necessary bend or curved properly embeded in floor or walls including covering of holes with round SS cover to give neat finsh look. Insallation shall be as per instruction of Architects. Unit- payment shall be made for length of pipe installed and visible. Rate included driling in RCC/Brick member/Flooring/necessary fastner as necessary for giving stable Railing	10		RMT	
21	Removing very carefully of Existing Tables, Side Tables, Cup board, Misc. other furnitures, Ceiling (If any) and existing wooden / Aluminium Partition including stacking debris and reusable material complete as directed including carting away debris all levels.	1		LOT	
	TOTAL COST OF FURNISHING WORK			Rs.	

=+ GST AS PER APPLICABLE

Sr. No.	Description	Quantity	Rate	Unit	Amount

NOTE:

1. **Rate includes dismentling existing furniture and storing/ standing the same at a location as directed by bank Nothing extra shall be paid for then.**

   Rate includes dismantling of existing gypsum Board & Armstrong False Ceiling and disposal complete as directed.

2. **Temporary shifting of Branch Furniture at convinient location as per the instruction of Architect/Bank. Rate includes creating/errecting counters, cash cabin arrangement of furniture to the entire satisfaction of Branch Manager complete as directed.by bank Nothing extra shall be paid for then.**

3. **In all furniture work, contractor shall make necessary cutout in panelling / partitions / wooden members to facilitate electrical/data cabelling and No extra amount shall be paid for this.**

4. **All internal surface (non visible surfaces) shall be provided with the 0.60 mm thick balacing laminate of aproved make & shade in the all Cash Counters/Tables/ Credenza, Storage Cup Board etc.**

Tender Amount(In Words) Rupees:

(SIGNATURE OF TENDERER/FIRM)

NAME OF TENDERER

(SEAL OF FIRM)
PLACE:
DATE: