

Proposed Electrical Work for Creche Area at Ground floor, Sun Tower, BKC, Mumbai

ELECTRICAL WORKS					
SI No.	Description	Qty	Unit	Rate	Amount
1	<u>Electrical Main Panel & DISTRIBUTION BOARD :</u>				
1.1	Supply of 12 Way SPN DB with 63A, DP MCB as incomer, outgoing 10amp sp 16 n0	1	Nos		-
2	<u>POWER AND CONTROL CABLES</u>				
2.1	3 Core X 6 Sqmm Cable (Asper acutal on site)	10.00	Mtr		-
3	<u>CABLE TERMINATIONS</u>				
3.1	4 Core X 6 Sqmm Alu Ar Cable	1	Nos		-
4	<u>LIGHT POINT /POWER POINT WIRING</u>				
4.1.	Primary light points controlled by one 6A switch (Make of switch to be given by the client) (Circuit Cost in not included)	15	Nos.		-
4.2	Secondary light points controlled by one 6A switch	34	Nos.		-
4.3	1no 5/ 13A plug socket controlled by 1no 15/5A switch and mounting plate with necessary accessories.	20	Nos.		-
5	<u>CIRCUIT WIRING</u>				
5.1	Supply, laying, connection and testing of 2 x 2.5 Sq.mm + 1 x 2.5 Sq.mm circuit wires from DB to Switch board and power socket to be laid through PVC conduit.	45	Mtr.		-
6	<u>LIGHT FIXURES</u>				
	installation, connection, testing & commissioning of following Light Fixtures				-
6.1	15 w led 8" by 8"	49.00	Nos.		-
7	<u>DATA & TELPHONE</u>				
7.1	25 MM PVC CONDUIT	60	MTR		-
7.2	CC TV cable	40	MTR		-
7.3	Speakar wire	40	MTR		-
	TOTAL				-

Light fitting Syska make
 Wire & Cable polycab FRLS
 Switche Plates legrand myris
 Mcb & Db Legrand Make