



Revised Price bid

Price bid for Supply, Installation, Testing and Commissioning of Air Conditioning units at 4th & 5th floor, Indra Complex, Bank of Baroda, Manjalpur, Vadodara. Rate shall be quoted by the bidder without GST.

PART A:

Sl. No.	Item	Unit	Quantity	Rate (₹)	Amount(₹)
1.	Supply of Split Type Units comprising of HIGHWALL MOUNTED TYPE units with Copper Condenser operating on R32 / R410 (3 star Minimum, Fix Speed Compressor) Supply Complete with Indoor, Outdoor, Cordless Remote, PM 2.5 Filter, Ag Clean filter , Electrical Wire & 3 mtr Copper kit. Cooling Capacity : 5350 W – 1.5 TR Make: Voltas / Panasonic / Bluestar / Toshiba / Carrier / Daikin	Nos.	34		
2.	Installation, Testing and Commissioning of 1.5 TR Split Type Units comprising of HIGHWALL MOUNTED TYPE units with Copper Condenser operating on R32 / R410 .(3 star Minimum , Fix Speed Compressor)Supply Complete with Indoor ,Outdoor, PM 2.5 Filter, Ag Clean filter , Electrical Wire & 3 mtr Copper piping Insulated with 13 mm Nitrile rubber of Class "O" & Supports. Cooling Capacity: 5350 W (with proper hole filing, copper pipe concealed inside wall) including chipping and minor civil work complete with all accessories as required.	Nos.	34		
3.	Supply, Installation, Testing and Commissioning of Refrigerant piping (beyond 3 Rmt) – insulated 0.80 wall thickness (or as specified by OEM) copper tube of Mandavi / Totalline make between indoor to outdoor unit, beyond 3 Rmt, of 1.5 TR hiwall split unit. The copper piping shall be insulated with 9mm thick Nitrile rubber insulated of 'O' Class of	Rmt.	25		



	KFlax/Armaflex/Superlon Make(copper piping concealed inside wall) in chipping and minor civil work complete with all accessories as required.				
4.	Supply, Installation, Testing and Commissioning of 2.5 Sq. mm x 4 core Copper Flexible cable (beyond 3 Rmt) from Indoor to outdoor communications for split ac.	Rmt	25		
5.	Supply and Fixing of drain pipe 25mm dia UPVC with insulation of Dutron/Supreme/Astral make – schedule 40 pipe white in color, joint properly glued with UPVC adhesive for water outlet from indoor unit (drain pipe concealed inside wall) including chipping and minor civil work complete with all accessories as required	Rmt.	50		
6.	Supply and Installation of MS angle iron stands for mounting 1.5 TR outdoor condensing unit complete with wall cutting, hole cutting, plastering etc. as required complete.	Nos.	34		
			Total Amount (A)		



PART B:

Comprehensive AMC for 2 Years for new installation after completion of warranty /Defect liability Period (DLP) of 1 year and 3 years for existing cassette units.

Sl. No.	Item	Unit	Quantity	Rate (₹)	Amount(₹)
1	Comprehensive AMC Charges of 1.5 TR split unit				
1.1	For 1st Year after DLP	Nos.	34		
1.2	For 2 nd Year after DLP	Nos.	34		
2	Comprehensive AMC Charges of 3 TR Cassette A/C unit <u>already installed of Voltas Make</u>				
2.1	For 1st Year (from date of work order)	Nos.	9		
2.2	For 2 nd Year	Nos.	9		
2.3	For 3 rd Year	Nos.	9		
3	Comprehensive AMC Charges of 2 TR cassette type A/C unit <u>already installed of Carrier Make</u>				
3.1	For 1st Year (from date of work order)	Nos.	4		
3.2	For 2 nd Year	Nos.	4		
3.3	For 3 rd Year	Nos.	4		
		Total Amount (B)			

SUMMARY OF PRICE BID

•	Total Part A	
•	Total Part B	
•	Grand Total	
	Grand Total In words	

* GST as applicable shall be paid extra over & above the quoted price as applicable.

** All the accessories identified by the manufacturer, so as to make a complete set, shall be a part of the item even if they are not specifically mentioned in the BOQ of the tender.