

## PART - II : PRICE BID (Per Flat)

Si.No	CARPENTRY (KITCHEN)	Qty	Unit	Rate	Amount
	Modular Kitchen Work - Profile Shutter				
1	Providing & fixing shutters below kitchen platform made up of 16 mm marine plywood with 16 mm marine ply framing and partition finished with hot/machine pressed laminate high gloss externally and internally with 0.80 mm white laminates with soft closing Hinges of Hetich or sleek or equivalent make and provision of handle as horizontal G- profile in all drawers and shutters.	44	Sq ft		
2	Providing & fixing stainless steel trollies 304 grade from 375mm to 500 mm deep with soft closing channel of Hettich or Sleek or equivalent make. (Cutlery trolley 1 No., cup & soccer 1 No Thali Basket 1 no., Pull out 6" 1 No. and plain Trollies 3 no and bin holder 1 No.	7	No.		
3	Providing and fixing Chimney of Elica / Kaff / Faber or equivalent Make.	1	no		
4	Providing and fixing overhead cabinets made up of 16 mm marine ply with profile shutters made up of aluminium profile with back painted toughened glass 4 mm thick. Cabinet finished externally with Hot/machine pressed high gloss laminate 1.00 mm thick and internally with 0.80 mm laminate with soft closing Hinges of Hettich / Hafele/Blum or equivalent make	24	Sq ft		
5	Providing and fixing encasing or covering made up of 16mm marine plywood with hot/machine pressed laminate to hide the Chinmey Exhaust pipe 6" dia above the cabinet above main platform and portion above chimney upto 300mm deep.	7	Rft		
	Wardrobe Work				
6	Making Wardrobe with 18 mm commercial plywood of Archid or equivalent make upto 22" deep finished with laminate (machine pressed) 1.00 mm thick of sunmica or equivalent make and internally with 0.80 mm thick white laminate.	158	sq.ft		
7	Providing and fixing 25mm dia heavy duty stainless steel curtain rods with brass support and decorative type end sockets. Base rate Rs 200 Rft.  Total (Excluding Tax)	50	RFT		
	Total for 13 Similar Flats				